



Engineering Services

Updated August 19, 2019

Pages Dairy Road Widening & Resurfacing

Project Photo



Current Status:

- JEA watermain design underway
- Construction to begin in January—
March 2020

Project Team Members:

Contractor: TBD

Construction Engineering Inspection: TBD

Project Manager: Robert T. Companion, PE

Project

Project Limits:

- Pages Dairy Road (CR 200A) from Felmor Road to Chester Road (2.64 miles)

Project Goals:

- Widen and resurface the roadway to 11' lanes with 5' paved shoulders / bike lanes

Construction Activities:

- Widen and mill & resurface the roadway to 11' lanes with 5' paved shoulders / bike lanes
- Regrade the ditches as required to accommodate new lane and shoulder widths
- Restore all driveways effected by construction activities
- Replace triple cross drain bridge

Project Schedule:

- Construction to begin no earlier than January 2020, and no later than March 2020
- Construction Duration is expected to be between 8-12 months
- All project work will be conducted at night to allow travel lanes be reopened during the day.